BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Improvements to Roads and drain at Rachenahalli, Srirampura and Nagawara Colony in Ward No.08 Jakkur.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	941.65	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	cum	204.60	Rupees Two Hundred Four and Sixty Paise Only
2	156.52	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	cum	6109.40	Rupees Six Thousand One Hundred Nine and Forty Paise Only
3	302.96	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	cum	6893.04	Rupees Six Thousand Eight Hundred Ninety Three and Four Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
4	18.73	Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Tonne	101387.00	Rupees One Hundred One Thousand Three
5	812.52	Providing and Fixing pre cast covering Slab 100mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge.	sqm	2072.00	Rupees Two Thousand Seventy Two Only
6	43.20	Providing and Fixing pre cast covering Slab 230mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge.	sqm	5037.00	Rupees Five Thousand Thirty Seven Only
7	941.65	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3)	cum	129.80	Rupees One Hundred Twenty
8	1205.31	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	t.km	105.60	Rupees One Hundred Five and

"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))